

**GLADSTONE**



**City of Gladstone  
REQUEST FOR PROPOSAL  
RFP # 2023  
Water Main and Service line  
Materials to be purchased after  
April 1, 2024 for summer  
construction season**

**DATE: 12/11/2023**

**INTENT**

The City of Gladstone requests proposals for Watermain and service line materials to be purchased after April 01, 2024 for the summer construction season.

**PROPOSAL SUBMITTAL**

Deadline and Proposal Opening will be at 1:00 pm, Monday December 18, 2023. Location of the opening will be at Gladstone City Hall, Commission Chambers, 1100 Delta Avenue, Gladstone, MI. 49837. All proposals must be submitted in **triplicate** in a sealed envelope clearly identifying the bid title. No fax or electronic proposals will be accepted. Submission requirements can be found on the City website at [https://www.gladstonemi.org/how\\_do\\_i/request\\_for\\_bids.php](https://www.gladstonemi.org/how_do_i/request_for_bids.php)

Mail Proposals to:

City of Gladstone  
Water Main & Service Line 2023  
ATTN: Kim Berry, City Clerk  
1100 Delta Avenue  
Gladstone, MI. 49837

**SCOPE OF WORK**

See attached Material List

**SCHEDULE**

Purchase after 04-01-2024 for summer 2024 construction season

**CONTACT INFORMATION**

If there are any clarifications required, please address them to the following:

Robert Spreitzer  
Water Department  
City of Gladstone  
1100 Delta Avenue  
Gladstone, MI. 49837  
906-428-3460 or 906-399-0764  
[rspreitzer@gladstonemi.gov](mailto:rspreitzer@gladstonemi.gov)

## BID PROPOSAL FOR WATERMAIN MATERIALS

CITY OF GLADSTONE

To be purchased after April 01,2024

ITEM	QTY	UNIT	DESCRIPTION	UNIT COST	TOTAL COST
1	800	LF	8" DIP, PC 350, SBT, CEMENT LINED, CABLE BOND		
2	3	@	8" R.S. GATE VALVE, MJ,		
3	6	@	2 PC. VALVE BOX,DD, WITH STAY-PUT COVERS,		
4	6	@	VALVE BOX BASE, NO. 6		
5	2	@	8" X 8" X 6" TEE, MJ for Hydrants		
6	2	@	8" X 8" X 8" X 8" cross, MJ		
7	1	@	8" X 6" reducer MJ for connection on cross to 6"		
8	3	@	6" R.S. GATE VALVE, MJ,		
9	11	@	6" MEGA LUG kit w/Bolts and gasket		
10	16	@	8" MEGA LUG kit w/Bolts and gasket		
11	0	LF	6" DIP, PC 350, SBT, CEMENT LINED, CABLE BOND, Hyd lead		
12	2	@	FIRE HYD., WATEROUS PACER, MJ, 5 1/4" VO, DDP, 5' BURY, TRAFFIC or EJIW Equal		
13	29	@	1" COMP. CORPORATION STOP, MUELLER H-15008 or Ford Equal		
14	29	@	1" COMP. CURB STOP, MUELLER H-15209 or Ford Equivalent		
15	29	@	1" CURB BOX . 6' EXT., ARCH BASE, LID W/ BRASS PLUG		
16	2100	LF	1" TYPE K COPPER TUBING, 100' ROLL,		
17	1	JOB	Delivery of Materials to City of Gladstone Water Plant		
				<b>TOTAL</b>	

\*\*NOTE: ALL MATERIALS MADE IN THE U.S.A.